



CLIENT:

Sustainment and
Restoration Services LLC

ROLE:

Subcontractor/
Self-Performing

PROJECT NUMBER:

10-19-0023

Contract Amount:

\$1,809,000.00

DATE COMPLETED:

Active

PROJECT HIGHLIGHTS:

- *Provided a 10-man 40 HR OSHA/Asbestos trained crew to clear cut 10 acres of heavily wooded area prior to excavating Impacted debris piles*
- *Established a work pad for office trailers and support zones*
- *Constructed access roads to work areas 2A-2B and various decon pads*
- *Segregated debris piles for recycling and disposal*
- *Cleared and prepared a lay down area for tree processing/chipping*
- *Constructed temporary decontamination pads*

NASA Plumb Brook



Buckeye Elm is currently contracted to performed site preparation services including installation of erosion control encompassing the work areas, tree clearing/processing, construction of access roads for ingress and egress and the removal, breaking, staging and crushing of concrete debris for remedial units 2A/2B at the NASA Plumb Brook Site located in Sandusky, Ohio.

TREE CLEARING

Buckeye Elm provided a 10-man OSHA and Asbestos Certified crew to clear cut approximately 10 Acres of trees in Level C PPE due to the presence of asbestos containing materials that was previously co-mingled into the debris pile in Areas 2A/2B. The tree clearing work was expeditiously and safely completed in an expedited time frame in order to meet the Indiana Bat deadline.



DEBRIS SORTING AND STAGING

Buckeye Elm is providing all labor and equipment to separate, and stage concrete debris comingled with massive amounts of steel, rebar, C&D materials and impacted contaminated soils. All wastes materials are being segregated into piles for offsite disposal at a Subtitle C landfill or concrete/steel recycler.

DECONTAMINATION

Temporary decontamination pads were setup at each operating unit in a decontamination reduction zone during the tree clearing work completed in the asbestos impacted area.

Proper scheduling and coordination with the field personnel allowed completion of the project within budget and ahead of time.



782 Hartford St. • Worthington, OH 43085
888.315.8663 • buckeye-elm.com